



FIRE DEPARTMENT SANTA CLARA COUNTY

14700 Winchester Blvd., Los Gatos, CA 95032-1818
(408) 378-4010 • (408) 341-4499 (fax) • www.sccfd.org



STANDARD DETAILS & SPECIFICATIONS	Spec No <u>C-2</u>
SUBJECT: Emergency Responder Radio Coverage Systems	Rev. Date <u>10/24/19</u>
	Eff. Date <u>10/01/19</u>
	Approved By <u>[Signature]</u>
	Page <u>1</u> of <u>15</u>

SCOPE

This standard applies to the installation of an emergency responder radio coverage, whether required by the California Building Code, local ordinance, or as an approved Alternate Method of Compliance thereto.

DEFINITIONS

Alternate Method of Compliance: An approved method of compliance that, in the opinion of the Fire Department, meets the intent of the provisions of the California Fire Code.

NFPA 72: Shall refer to the National Fire Protection Association Standard 72 – National Fire Alarm and Signaling Code.

SCCFD: Shall refer to the Santa Clara County Fire Department.

REQUIREMENTS

- I. **Emergency responder radio coverage in new buildings.** Approved radio coverage for emergency responders shall be provided within all buildings meeting any one of the following conditions:
 - A. There are more than 3 stories above grade plane (as defined by the Building Code Section 202);
 - B. The total building area is 30,000 square feet or more;
 - C. The total basement area is 5,000 square feet or more;

- D. Where required by the fire code official and radio coverage signal strength levels are not consistent with the minimum levels set forth in Section 510.4.1.

Exceptions:

1. Where approved by the fire code official, a wired communication system in accordance with Section 907.2.13.2 of the California Fire Code shall be permitted to be installed or maintained in lieu of an approved radio coverage system. When this option is implemented, a fire command room shall be required.
2. Where it is determined by the fire code official that the radio coverage system is not needed.
3. In facilities where emergency responder radio coverage is required and such systems, components or equipment required could have a negative impact on the normal operations of that facility, the fire code official shall have the authority to accept an automatically activated emergency responder radio coverage system.
4. Buildings and areas of buildings that have minimum radio coverage signal strength levels of the Silicon Valley Regional Interoperability Authority (SVRIA) P25 Phase 2 700 MHz Digital Trunked Radio System within the building in accordance with Section 510.4.1 without the use of an indoor radio coverage system.

The radio coverage system shall be installed and maintained in accordance with this Standard and with the applicable provisions of NFPA 1221, Standard for the Installation, Maintenance and Use of Emergency Services Communications Systems.

The coverage shall be based upon the existing coverage levels of the public safety communication systems of the jurisdiction at the exterior of the building. This section shall not require improvement of the existing public safety communication systems.

- II. Obstruction by new buildings.** No obstruction of the public safety system backhaul shall be allowed without an approved mitigating plan.

III. Emergency responder radio coverage in existing buildings. Existing buildings shall be provided with approved radio coverage for emergency responders as required in Chapter 11 of the California Fire Code.

IV. Permits

A. Permit required. A construction permit for the installation of or modification to emergency responder radio coverage systems and related equipment is required as specified in Section 105.7.5 of the 2016 California Fire Code.

Maintenance performed in accordance with this code is not considered a modification and does not require a permit. A frequency change made to an existing system is considered to be new construction and will require a construction permit.

B. SVRIA system registration. Prior to issuance of a construction permit, systems must be registered with the SVRIA and proof of registration shall be submitted to the fire code official upon plan submittal.

V. Plans

A. General Requirements

1. Plans and attachments shall be clearly labeled and legible.
2. Plans and all revisions to the plans shall be dated. If utilizing an existing drawing or portion of a drawing, the area of work shall be highlighted and clouded with an appropriate symbol (delta). Provide a revision list with a symbol, date, description, and initials.
3. When making alterations, additions, or deletions to an existing system, all existing devices and equipment shall be shown and properly identified on the floor plan and system riser (single-line) diagram.
4. Plans shall include a title sheet, an equipment list, a written standard operating procedure, a floor plan, a system riser diagram, and secondary power calculations. See Title Sheets section herein.
5. Attachments shall include the manufacturer's specification sheets for all equipment and devices such as; cables, amplifiers, ups, batteries and antenna; indicating the FCC certification. See Attachments section herein.

Note: Failure to provide any of the information required will result in plans being disapproved.

B. Title Sheet

1. The front sheet shall contain the following information:
 - a) Project name and address of the project.
 - b) The designer's full name (no initials, pseudonyms, acronyms, or aliases) FCC License number and signature. The designer of record shall be responsible for the entire system being worked on.
 - c) Business name, address, and California Contractor's License number and FCC issued License of the installing contractor. If the designer of the ERRC system is not the installing contractor, the following shall be clearly indicated/printed on the plans:
 - i. **DESIGNED BY** – followed by the designer's business name, address, designer of record's full name and signature. See CFC 510.5.2 for qualifications.
 - i. **INSTALLING CONTRACTOR** – followed by the installing contractor's business name, address and California Contractor's License number. See CFC 510.5.2 for qualifications.
 - d) Name and type of supervising station service monitoring system as per NFPA 1221 section 9.6.13.
 - e) Occupancy group(s) of building or area as defined by the California Building Code.
 - f) Number of basements, number of stories above basement, building height, total building area, and building construction type.
 - g) Scope of work. If the scope of work is the demolition of an existing ERRC system, justification for removal shall be provided.
 - h) Description of transmission zone assignments such as complex name, address, or campus and designation.

- i) A note stating that the design and installation complies with the CFC (2016 editions), NFPA 72 & 1221 (2016 editions), the California Electrical Code (2016 edition), the California Building Code (2016 edition), and the Santa Clara County Fire Department ordinances, policies, and standards.
 - j) A clear site map and/or vicinity map.
 - k) All other pertinent notes.
2. A key plan of the building and/or complex indicating the street location and the ERRC System Controls within the building shall be provided.
 3. State the required performance objective of the ERRC per CFC 510.4 and NFPA 1221, section 9.6. Should the codes conflict, the most stringent shall prevail.

C. Equipment List

1. Provide the model number, manufacturer's name, description, quantity, and symbols to be used (legend) for each device, equipment, and conductors proposed to be installed.
2. The symbols used on the plans shall match the legend. Strike out any "typical" symbols that do not pertain.

D. Floor Plan – the following shall be clearly identified:

1. Scale used and a graphical representation of the scale. The minimum scale for ERRC plans is 1/8" = 1'-0". Metric scale shall not be accepted.
2. Room and room names.
3. The locations of partitions, non-rated walls, and rated walls.
4. The location of all Emergency Responder equipment.
5. Power and Panel locations.
6. Raceway outing.
7. Conduit and conductor size.
8. Roof plan showing location(s) of antennae.
9. Location(s) of In Building Antennae.
10. Band width.

E. Rise Diagram – provide the following:

1. Single-line wiring diagram (riser diagram) that shows the interconnection of equipment of the whole system.

2. Type and size of wire or conductor to be used.
 3. Schematic drawing of electrical system and backup power.
- F. Detail Diagram – Show Supervisory points from repeater.
- G. Calculations
1. Secondary power calculation – See note below.
 - a) **Note:** Secondary power supply – Emergency responder radio coverage systems shall be provided with an approved secondary source of power per 2016 NFPA 1221 section 9.6.12 in addition to CFC 510 section 4.2.3 and 604.2.3.
- H. Signal Propagation Map – Provide a map indicating the signal strengths as designed and then as installed by As-Built. These maps are generally printed in color; however, they are scanned in black and white (B&W). The map(s) must be graphically distinct such that having been scanned into B&W it/they will still demonstrate the system design.
- I. Attachments
1. Manufacturer's specification sheets for all devices, equipment, and materials to be used shall be submitted, including the cables, amplifiers, ups, batteries, antenna and transponder to the supervising station. Highlight on the cut sheet which device or equipment is being used, the listing information, and the application per listing.

VI. Technical Requirements

Systems, components, and equipment required to provide emergency responder radio coverage systems shall comply with Section 510.4.1 through 510.4.2.5. V

A. Radio signal strength. The building shall be considered to have acceptable emergency responder radio coverage when signal strength measurements in 90 percent of all areas on each floor of the building meet the **Minimum signal strength into the building** and **Average signal strength out of the building** requirements specified in items 1 and 2 below.

Exception: Critical areas, such as the fire command center(s), the fire pump room(s), interior exit stairways, exit passageways, elevator lobbies, standpipe cabinets, rescue air filling stations, sprinkler sectional valve locations, and other

areas required by the fire code official, shall be provided with 99 percent floor area radio coverage.

1. **Minimum signal strength into the building.** A minimum signal strength of -95 dBm shall be receivable in 90% of the area of each floor within the building when transmitted from the Silicon Valley Regional Interoperability Authority (SVRIA) P25 Phase 2 700 MHz Digital Trunked Radio System.
 2. **Average signal strength out of the building.** A maximum signal strength of -95 dBm shall be received by the Silicon Valley Regional Interoperability Authority (SVRIA) P25_Phase 2 700 MHz Digital Trunked Radio System at the donor site when transmitted from 90% of the area of each floor within the building.
- B. Signal strength differential.** The system shall be designed to ensure that there is a minimum 15 dB difference between the interior and exterior signal strength.
- C. Delivered audio quality.** The radio coverage system shall provide a minimum delivered audio quality of level 3.4 (DAQ “3.4”) on each floor of the building or structure. DAQ 3.4 constitutes audio quality that makes speech understandable with repetition only rarely required with some noise and distortion (TSB88).
- D. Building conduit and pathway survivability.** All new buildings shall be constructed with not less than a two-inch (2”) conduit within a minimum of a two-hour fire rated assembly, which extends from the lowest level/floor to the roof.
1. Installed riser cable shall be protected by a 2-hour-rated enclosure.
- Exception:** In buildings with 1-hour rated construction, the riser cable shall be mechanically protected by metal conduit, which can be routed through a sprinkled 1-hour rated enclosure.
2. All feeder cable shall be protected by an automatic sprinkler system in accordance with NFPA 13 or installed within approved metal raceway.
 3. All radio cable (riser and feeder) is required to be plenum-rated. Cable other than radio cable is allowed to comingle with the radio cable in the conduit provided it is listed, shielded cable that will not interfere with the radio cable.

4. At each floor and the roof, an opening shall be made to allow easy access to the conduit from the ceiling.
5. Access in either the form of a drop ceiling or access panel shall be made along hallways and through firewalls.
6. All floors of the subterranean parking garages shall meet access, conduit installation and rating requirements.

E. System design. The emergency responder radio coverage system shall be designed in accordance with Section 510.4.2.1 through 510.4.2.5.

1. **Amplification systems allowed.** Buildings and structures that cannot support the required level of radio coverage shall be equipped with a radiating cable system, a distributed antenna system with Federal Communications Commission (FCC)-certified, Class A public safety grade signal boosters (amplifiers) designed for the frequencies specified by the fire code official, in order to achieve the required adequate radio coverage.
2. **Technical criteria.** The fire code official shall provide the various frequencies required, the location of radio sites, effective radiated power of radio sites, and other supporting technical information upon request by the building owner or owner's representative.
 - a. The Public Safety radio system, extending from the head-end amplifier to the distributed antennas shall not be combined with other DAS systems installed in the building.
 - b. A single antenna system is allowed provided the antennas are capable of passively distributing all frequencies between 698MHz and 2.7GHz and the hardware for both Public Safety and wireless carrier frequencies are completely separate with necessary filters. The single antenna system must also be tested and certified by a qualified contractor.
 - c. Where fiber distribution systems are used to extend the Public Safety radio system throughout the building or to other buildings, the horizontal fiber runs shall be enclosed in conduit meeting at least the building conduit requirements in Section 510.4.1.5.
3. **Power supply sources.** Emergency responder radio coverage systems shall be provided with at least two independent and reliable power supply sources

conforming to NFPA 72 and the Electrical Code, one primary and one secondary. The standby power supply shall be an approved UPS system capable of operating the emergency responder radio coverage system for a duration of not less than 24 hours. When primary power is lost, the power supply to the emergency responder radio coverage system shall automatically transfer to the standby power supply.

Emergency power off (EPO). The UPS system shall be equipped with an emergency power off (EPO) switch in a location approved by the fire code official. The EPO shall disconnect both the circuit breaker and secondary power supply simultaneously.

4. **Signal booster requirements.** If used, signal boosters shall meet the following requirements:
 - a. All signal booster components shall be contained in a National Electrical Manufacturer's Association (NEMA) 4-type waterproof cabinet.
 - b. Battery systems used for the emergency power source shall be contained in a NEMA 4-type waterproof cabinet.
 - c. The signal booster system and power supply(ies) shall be electrically supervised and monitored in accordance with NFPA 1221. For buildings without a fire alarm system, a dedicated monitoring panel in accordance with NFPA 72 shall be provided to annunciate automatic supervisory and trouble signals for the signal booster system and power supply(ies) and sound an audible signal at a constantly attended location.
 - d. Equipment shall have FCC certification prior to installation.
5. **Additional frequencies and change of frequencies.** The emergency responder radio coverage system shall be capable of modification or expansion in the event frequency changes are required by the FCC or additional frequencies are made available by the FCC.

VII. BDA/DAS Design, Optimization, and Acceptance Process.

The following sections outline relevant information about optimizing BDA/DAS systems that will operate in conjunction on the Silicon Valley Regional Communications System (SVRCS) Project 25 Land Mobile Radio (LMR) system

frequencies and ensure an optimal DAS/BDA design and alignment to avoid negative impact to the P25 LMR system.

A. System Technical Information. To ensure BDA/DAS system optimal design to operate efficiently with the SVRCS P25 system, contact the County Communications Engineering (contact information listed below) for detailed SVRCS antennae systems design. BDA/DAS technical guidelines that are pertinent to BDA/DAS preliminary design requirements can be found on the SVRIA website www.svria.org and/or by contacting Santa Clara County Communications Radio Shop at (408) 977-3222 Monday through Friday, 8am to 5pm, and/or email at radioshop@911.sccgov.org.

1. After final installation of the BDA/DAS system, vendors must contact the Santa Clara County Communications Radio Shop to schedule BDA/DAS optimization/alignment and testing.
2. Once the BDA/DAS optimization is scheduled, test radios are available for sign out at the Santa Clara County Radio Shop that will be used to validate the BDA/DAS operation meets DAG 3.4 or better.
3. Upon completion of BDA/DAS optimization and testing, a pass-through document will be generated by the Santa County Communications System Technician assigned to optimization process. This document will be forwarded to the fire code official and a copy maintained on the premises, filed with the SVRIA official, and made available to the Fire Department and the BDA/DAS vendor on request.

B. The fire code official will not approve BDA/DAS operation for building occupancy unless this pass-through document is completed and received by fire code official.

VIII. Installation Requirements

The installation of the public safety radio coverage system shall be in accordance with Section 510.5.1 through 510.5.6.

A. Approval prior to installation. Amplification systems capable of operating on frequencies licensed to any public safety agency by the FCC shall not be installed without prior coordination and approval of the fire code official.

B. Minimum qualifications of personnel. The minimum qualifications of the system designer, lead installation personnel and personnel conducting radio system testing shall include possession of both of the following:

1. A valid FCC-issued general radio operators license; and
2. Certification of in-building system training issued by one of the following:
 - a. Associated Public Safety Communications Officials (APCO),
 - b. The manufacturer of the equipment being installed,
 - c. or other industry recognized institutions.

All design documents and all tests shall be documented and signed by a person meeting the minimum qualification noted in this section.

C. Acceptance test procedure and system certification. Upon completion of installation, the building owner shall have the radio system tested to verify that two-way coverage on each floor of the building is in accordance with Section 510.4.1. The test procedure shall be conducted as follows:

1. Talk-back testing from a site to the Silicon Valley Regional Interoperability Authority (SVRIA) P25 Phase 2 700 MHz Digital Trunked Radio System shall use local agency radio(s) on the designated test channel(s) and may be witnessed by a representative of the Fire Department.
2. Each floor of the building shall be divided into a grid of 20 approximately equal test areas.
3. The test shall be conducted using a calibrated portable radio of the latest brand and model used by the agency talking through the agency's radio communications system.
4. In the event that three of the test areas on a floor fail the talk back test, in order to be more statistically accurate, the floor shall be permitted to be divided into 40 equal test areas. If the system fails the 90% coverage requirement for the 40-area test, the emergency responder radio system shall be altered to meet the 90-percent coverage requirement.

Exception: Critical areas as defined by the fire code official shall be provided with 99 percent floor area coverage.

5. A test location approximately in the center of each test area shall be selected for the test, with the radio enabled to verify two-way communications to and from the outside of the building through the Silicon Valley Regional Interoperability Authority (SVRIA) P25 Phase 2 700 MHz Digital Trunked Radio System. Once the test location has been selected that location shall represent the entire test area. Failure in the selected test location shall be considered failure of that test area.
6. The test for emergency responder radio coverage will be considered passed when 90% of the test locations on each floor are able to pass two-way communications to and from the outside of the building.

Exception: Critical areas as defined by the fire code official shall be provided with 99 percent floor area radio coverage.

7. The gain values/output levels of all amplifiers shall be measured and the test measurement results shall be kept on file with the building owner so that the measurements can be verified during annual tests. In the event that the measurement results become lost, the building owner shall be required to rerun the acceptance test to reestablish the gain values.
8. As part of the installation a spectrum analyzer or other suitable test equipment shall be utilized to ensure spurious oscillations are not being generated by the subject signal booster. This test shall be conducted at time of installation and subsequent annual inspections.
9. Individuals conducting initial benchmark and system acceptance tests shall meet the minimum qualifications in accordance with Section 510.5.2. All test results are required to be validated by an approved third party, independent of the system designer and installer.

Prior to issuance of the building Certificate of Occupancy, a system acceptance test report shall be submitted to the fire code official, maintained on the premises and be made available to the Fire Department upon request. The report shall verify compliance with Section 510.5.4d, and include the emergency responder radio coverage system equipment data sheets, diagram showing device locations and wiring schematic, and a copy of the electrical permit and system certification letter.

- D. Compliance.** The emergency responder radio coverage system installation and components shall also comply with all applicable federal regulations, including, but not limited to, FCC 47 CFR Part 90.219.
- E. Location of equipment.** For buildings without a fire command center the communications control equipment shall be located inside the building near the fire alarm control panel, or other approved location.
- F. Signage.** Buildings equipped with an emergency responder radio coverage system shall be identified by an approved sign located above or near the building key box stating: "Radio System Installed".

IX. Maintenance

The emergency responder radio coverage system shall be maintained operational at all times in accordance with Sections 510.6.1 through 510.6.5.

A. Testing and proof of compliance. The emergency responder radio coverage system shall be inspected and tested annually or whenever structural changes occur including additions or remodels that could materially change the original field performance tests. Individuals conducting the tests shall meet the minimum qualifications in accordance with Section 510.5.2. All test results are required to be validated by an approved third party, independent of the system designer and installer. Testing shall consist of the following:

1. In-building coverage test as described in Section 510.5.3.
2. Signal boosters shall be tested to verify that the gain/output level is the same as it was upon initial installation and acceptance.
3. Backup batteries and power supplies shall be tested under load of a period of 1 hour to verify that they will properly operate during an actual power outage. If within the 1-hour test period the battery exhibits symptoms of failure, the test shall be extended for additional 1-hour periods until the integrity of the battery can be determined.
4. All other active components shall be checked to verify operation within the manufacturer's specifications.

5. At the conclusion of the testing, a report, which shall verify compliance with Sections 510.5.3 and 510.6 shall be submitted to the fire code official and a copy maintained on the premises and made available to the Fire Department upon request.
- B. Additional frequencies.** The building owner shall modify or expand the emergency responder radio coverage system at their expense in the event frequency changes are required by the FCC or additional frequencies are made available by the FCC. Prior approval of a public safety radio coverage system on previous frequencies does not exempt this section.
- C. Field testing.** Agency personnel shall have the right to enter onto the property at any reasonable time to conduct field testing to verify the required level of radio coverage.
- D. Qualifications of testing personnel.** All tests shall be documented and signed by a person meeting the minimum qualifications set forth in Section 510.5.2.
- E. Continuing operation/supervision.** The occurrence of any fault in an emergency responder radio coverage system where the system function is decreased shall result in the transmission of a supervisory signal to a supervisory service. Systems that are out-of-service for more than 8 hours require notification to the fire code official.

Design Details for Approved Building Signage Required in Section VI-F of this Standard:

**6" x 8" Sign
½" Lettering
2" x 4" Graphic
Red Background with
White Letters and
Graphic**



Radio System Installed